

Material Order Sheet

Foundations	Description	Quantity	Unit	Unit Cost	Total
	38 x 38 x 800mm long stakes	85	Stakes	£0.83	£70.55
	Sawn 25 x 100mm (treated)	64	LM	£1.05	£67.20
	Brick line Marshalltown Hi-Viz 28x11x49cm x 76M	3	Rolls	£5.01	£15.03
	Line Marker (yellow spray) No-Nonsense 750ml	2	Cans	£6.48	£12.96
	Reinforcement Bar Mildsteel 16mm per meter	168	LM	£0.72	£120.96
	Reinforcement Bar Mildsteel 20mm per meter	84	LM	£1.04	£87.36
	Spacers Plastic 65/75mm x 125	2	Pack	£39.87	£79.74
	Concrete foundation (6 m3 loads)	26.5	M3	£69.40	£1,839.10
Total				£2,292.90	

Ground Floor	Description	Quantity	Unit	Unit Cost	Total
	Allowed PC. of £250.00 per Thousand	443	Bricks	£0.25	£110.75
	Trench Block Thermalite 255mm	421	Blocks	£3.04	£1,279.84
	Solid Concrete Block 100mm	135	Blocks	£1.27	£171.99
	Bricking Sand 1 ton	3	Tons	£36.22	£108.66
	Cement (25kg Bag)	22	Bags	£2.99	£65.78
	Wall Tie Butterfly Steel 225mm	93	No	£0.22	£20.46
	Concrete Lintel 20 x 100 x 1200mm	8	No	£6.51	£52.08
	150mm Beams at 450mm Centres	27	M2	£22.51	£607.77
	Plastering Sand (25kg Bag)	7	Bags	£1.80	£12.60
	Lean Mix (3 m3 Loads)	1.5	M3	£74.00	£111.00
	Additional Cost For Part Load	1.5	M3	£25.00	£37.50
	Polythene 100 (Black) 4 x 25m	1	Roll	£30.02	£30.02
	Crushed Concrete (20 ton loads)	103	Tons	£16.65	£1,714.95
	Bricking Sand (5 ton loads)	2	Tons	£27.35	£54.70
	Radon Barrier Green 15 x 4m 360mu	2	Rolls	£105.64	£211.28
	Concrete Oversite (6 m3 loads)	10	M3	£89.90	£899.00
	Floor Insulation Kingspan Kooltherm K3 1200 x 2400 x 40mm	35	Sheets	£22.43	£785.05
	Floor Insulation Kingspan TF70 2400 x 1200 x 25mm	1	Sheets	£11.50	£11.50
	A142M Mesh 3600 x 2000 mm	28	Sheets	£23.84	£667.52
	Spacers Plastic 40/50mm x 200	1	Pack	£39.87	£39.87
	Spacers Wire Chairs 200mm A Frame 25 x 2m	62	No	£3.75	£232.50
Total				£7,224.82	

Walls	Description	Quantity	Unit	Unit Cost	Total
	Leicester Red (IBSTOCK)	11286	Bricks	£0.35	£3,950.10
	Lightweight Block 100mm	2507	Blocks	£0.76	£1,905.32
	Allowed PC of £400.00 per Thousand	2152	Bricks	£0.40	£860.80
	DPC. 100mm x 30LM	10	Rolls	£3.90	£39.00
	Bricking Sand 1 ton	15.5	Tons	£36.22	£561.41
	Cement (25kg Bag)	103	Bags	£2.99	£307.97
	Wall Tie Butterfly Steel 200mm	998	No	£0.19	£189.62
	Wall Insulation Cavity 50 x 1200 x 455m (12pp)	27	Packs	£14.52	£392.04
	Plasterciser 5 litre	9	No	£4.00	£36.00
	Clay Flue Liner 185mm Int Dia 180mm Tall	39	No	£10.55	£411.45
	Clay Flue Liner 225mm Int Dia 300mm Tall	3	No	£13.50	£40.50
	Milner Scored Fire Back (450mm Height)	1	No	£60.00	£60.00
	Roll Top Chimney Pot (900mm Length)	1	No	£100.70	£100.70
	Pipe Plastic 100mm 6m Length	2	No	£16.17	£32.34
	Bend 87.5 Deg Single Socket PCVu	2	No	£5.95	£11.90
	Air Brick 220 x 145mm	2	No	£3.26	£6.52
	Louvre Vent 229 x 76 x 229	1	No	£0.59	£0.59
	Cavity Closer Rigid 100mm x 2.5m	64	LM	£12.17	£778.88
Total				£9,685.14	

Windows and Doors	Description	Quantity	Unit	Unit Cost	Total
	1.2 x 1.2 Softwood Window	14	No	£113.41	£1,587.74
	1.774 x 1.2 Softwood Window	3	No	£113.41	£340.23
	1.832 x 2.076 Hardwood Front Doorframe+2 Side Frame	1	No	£366.23	£366.23
	2.41 x 2.1 Hardwood Sub Frame	1	No	£92.60	£92.60
	1.8 x 2.1 Hardwood French Doorframe	2	No	£300.00	£600.00
	Window Anchor 8 x 100mm pack of 10	31	Boxes	£0.97	£30.07
Total				£3,016.87	

This is a sample. This report continues for every section of the works.