Quotation for the work: RENOVATION & RECTIFICATION OF DIORAMAS INSIDE BOAT BUILDING GALLERY OF ODISHA STATE MARITIME MUSEUM, JOBRA, CUTTACK.

Sealed quotations from the intending eligible bidders having registration certificate, PAN card and VAT clearance will be received in office of the Odisha State Maritime Museum, Jobra, Cuttack upto 07.03.2015 at 3:00 PM and will be opened on the same day in presence of quotationer or their authorized agents

The undersigned reserves the right to reject any or all quotation without assigning any reason thereof

Sl. No.	Description of items	Quantity	Unit	Rate	Amount In Rupees
1	2	3	4	5	6
1	Brick work in K.B bricks 25 cm X 12 cm X 8 cm size having crushing strength not less than 75 kg / cm2 dimension tolerance + 8% in cm in foundation and plinth	7.98	Cum	3650.70	29132.58
2	Removing of exhibits from diorama & dismantling the decorated artifacts etc. complete(Labour only) for 4 nos. of Diorama	4	Per Diorama	5000.00	20000.00
3	Cement concrete (1:1.5:3) with 12mm size hard granite chips for R.C.C work including cost conveyance and royalties etc complete as per direction of the Engineer-in-charge cement concrete slab over the stage of Diorama.	2.837	Cum	6104.30	17317.89
4	Reinforcement for R.C.C. work including cutting, bending and tying the grill and placing in position including cost of binding wire 18 to 20 gauge and reinforcement steel etc complete. As directed by Engineer-in-charge	2.122	Qntl.	6441.50	13668.86
5	Properly reposition of removed exhibits and making artifacts in the diorama with fiber coating for 4 nos. of diorama	4	Per Diorama	15000.00	60000.00
6	Labour charge for dismantling and refixing of BWR plywood of 19mm thick fixed as side wall of Diorama including colouring & inside electric wiring etc complete.	4	Per Diorama	25000.00	100000.00
7	Cost of BWR plywood 19mm thick	47.36	Sqm.	865.00	40966.40
				Total	**Rs. 2, 81,085.73**
				Say	**Rs. 2, 81,086.00**

(Eleven items only)

My quoted rate is.....**Excess/ Less/ As per S/R (both in Figure & Word)** over the estimated cost of **Rs. 2, 81,086.00**

Signature of Agency

Cuttack 1.3.15

Director
Odisha State Maritime Museum
Jobra, Cuttack