Project Quotation

Project: CONCRETE PRIMARY SCHOOL ADDITION
Architect: EASLEY, SC
Engineer:
Bid Date:
Quote Date: Thursday, July 14, 2016

Item Number & Description	***Size***	***List***	***Net***

DISCLAIMER STATEMENT: This QUOTATION for materials is specific to the above- Mentioned project and is BASED ON OUR INTERPRETATION OF THE SPECIFICATIONS. As Such, this quotation is subject to architect/engineer approval. Wade Specification Drainage is not responsible for late addendum of specification changes. Wade Specification Drainage is not responsible for product Compliance to local, state or federal codes or legislation. CURRENT TERMS AND CONDITIONS OF MANUFACTURER WILL APPLY.

UNLESS OTHERWISE INDICATED WITHIN THE BODY OF THIS QUOTATION, THE PRICING AND TERMS OF THIS OFFER ARE VALID FOR THIRTY (30) DAYS.

LAV-1 CARRIER

WADE SERIES 520

Single lavatory carrier with round up-rights, rectangular base feet, cast iron concealed arms & non-slip locking devices.

520 **$696.00**

WHD-1

WADE SERIES 8708 **Wall Thickness**

Mild temperature wall hydrant with 1/4 turn cartridge, bronze casing, 3/4" hose connection, box with hinged cover & anti-siphon backflow preventer.

With satin finish nickel bronze (-1) **CC** **$988.00**

FCO

WADE SERIES 8000 **Pipe Size: IC, NH OR TY**

Cast iron cleanout with threaded, adjustable housing, flange ferrule, ABS plug & scoriated top.

With satin finish nickel bronze top (-1)

Outlet	
2"	**$440.00**
3"	**$464.00**
4"	**$622.00**
5"&6"	**$1,013.00**
8"	**$1,128.00**

Suffix Options (As Required)		ADD
-S	Square Cover	N/C
-T	Round Tile Floor Cover	N/C
-TS	Square Tile Floor Cover	N/C
-U	Round Terrazzo Floor Cover	$245.00
-US	Square Terrazzo Floor Cover	$245.00
-VP	vandal proof	$49.00
-X	Heavy Duty Cover (Standard on -12)	$110.00
-75	Bronze Plug in Lieu of ABS (2",3",4")	$135.00
-75	Bronze Plug in Lieu of ABS (6",8")	$432.00

WCO

WADE SERIES 8304 **Size:**

	Round wall cleanout access cover with center screw.		
	Cleanout ferrules & tees are optional.		
	With satin finish stainless steel top (-85)	**6"**	**$98.00**
		8"	**$118.00**
		10"	**$216.00**
Suffix Options (As Required)			ADD
-COF2	2" No-Hub Cleanout Ferrule With ABS Plug		$66.00
-COF3	3" No-Hub Cleanout Ferrule With ABS Plug		$103.00
-COF4	4" No-Hub Cleanout Ferrule With ABS Plug		$143.00
-COF5	5" No-Hub Cleanout Ferrule With ABS Plug		$214.00
-COF6	6" No-Hub Cleanout Ferrule With ABS Plug		$295.00
-COT2	2" No-Hub Cleanout Tee With ABS Plug		$159.00
-COT3	3" No-Hub Cleanout Tee With ABS Plug		$199.00
-COT4	4" No-Hub Cleanout Tee With ABS Plug		$311.00
-COT5	5" No-Hub Cleanout Tee With ABS Plug		$584.00
-COT6	6" No-Hub Cleanout Tee With ABS Plug		$887.00
-VP	vandal proof		$49.00
-75	Bronze Plug in Lieu of ABS (2",3",4")		$135.00
-75	Bronze Plug in Lieu of ABS (6")		$432.00